

## CYFOETH NATURIOL CYMRU

### CYHOEDDI BWRIAD I BEIDIO Â PHARATOI DATGANIAD AMGYLCHEDDOL (Rheol 5 Rheoliadau Asesu Effaith Amgylcheddol (Gwaith Gwella Draeniad Tir) 1999 fel y'u diwygiwyd gan OS 2005/1399 ac OS 2006/618)

#### Daliwr Coed Llanfair Talhaearn-Nant Barrog

Hysbysa Cyfoeth Naturiol Cymru y bwriada wella amddiffynfeydd llifogydd ar Nant Barrog yn Llanfair Talhaearn yn yr ataliwr llaid uwchlaw Smithy Hill (NGR SH 927 701). Bydd y gwaith gwella arfaethedig yn cynnwys y canlynol: gosod daliwr coed cadarn uwchlaw'r sgrîn sbwriel y brif geuffos, y gellir ei gyrraedd, ei gynnal a'i gadw gan weithwyr cyflawni Gweithrediadau CNC, ac a fydd yn amddiffyn rhag cau'r geuffos. Bydd yn disodli daliwr coed a osodwyd yn 2012. Bydd y daliwr yn 5m o led, yn ymestyn o'r naill lan i'r llall, ac yn 1.5m uwch lefel gwely'r afon, yn y diwedd.

Barn Cyfoeth Naturiol Cymru yw nad yw'r gwaith gwella'n debyg o effeithio'n sylweddol ar yr amgylchedd, ac ni fwriada baratoi datganiad amgylcheddol yn ei gylch.

Dylai unrhyw un sy'n dymuno gwneud sylwadau ynghylch effeithiau amgylcheddol tebygol y gwaith gwella arfaethedig, neu sydd ag angen rhagor o wybodaeth er mwyn gwneud hynny, ysgrifennu i'r cyfeiriad isod o fewn 28 diwrnod i ddyddiad cyhoeddi'r hysbyseb hon.

*Sherron Kitchen, Rheolwr Cynllun, CNC, Ffordd Caer Bwcle, Sir y Fflint CH7 3AJ*

## NATURAL RESOURCES WALES

### ANNOUNCEMENT OF INTENTION NOT TO PREPARE AN ENVIRONMENTAL STATEMENT (Regulation 5 of the Environmental Impact Assessment (Land Drainage Improvement Works) Regulations 1999 as amended by SI 2005/1399 and SI 2006/618)

#### Llanfair TH-Nant Barrog Tree catcher

Natural Resources Wales gives notice that it proposes to carry out improvement works to the flood defences on Nant Barrog in Llanfair Talhaearn at the Silt trap upstream of Smithy Hill (NGR SH 927 701). The proposed improvement works will involve the following: construction of a robust tree catcher, further upstream of the main culvert trash screen, which is accessible and maintainable by NRW Operations Delivery Teams and which provides a first stage defence to culvert blockage. This will replace the temporary tree catcher put in place during 2012. The structure will be 5m wide spanning the watercourse and have a finished height 1.5m above bed level.

Natural Resources Wales considers that the improvement works are not likely to have significant effects on the environment and does not intend to prepare an environmental statement in respect of them.

Any person wishing to make representations in relation to the likely environmental effects of the proposed improvement works or require any further information should do so, in writing, to the address specified below, within 28 days of the date of publication of this notice.

*Sherron Kitchen, Project Manager, NRW, Chester Road Buckley, Flintshire CH7 3AJ*